



## TEHAMA COUNTY PUBLIC WORKS

9380 SAN BENITO AVENUE, GERBER, CA 96035

P.: (530) 385-1462 F: (530) 385-1293

[HTTP://WWW.TEHAMACOUNTYPUBLICWORKS.CA.GOV/](http://www.tehamacountypublicworks.ca.gov/)

### **ADDENDUM #1** **TEHAMA COUNTY BUS SHELTER INSTALLATION PROJECT** **PLANS AND SPECIAL PROVISIONS** **COUNTY PROJECT NUMBER: 973037**

- Addenda Issuance Date: March 12, 2015
- Bid Opening Date/Time: March 18, 3:00 PM

#### **ADDENDUM #1; ITEM A:**

Refer to the "Notice to Bidders" of the Bid Book.

The bid submission deadline has been extended to April 1, 2015 at 3:00 PM.

All bid opening references to March 18, 2015 shall be omitted.

#### **CONFIRMATION OF ADDENDA RECEIPT**

Be sure to acknowledge your receipt of this addendum on the Bid Signature Page to remain as a responsive bidder.

Tehama County Public Works

Signature: Kevin Rosser

Name: Kevin Rosser, PE

Title: Senior Civil Engineer of Public Works

Date: 3.12.15



## TEHAMA COUNTY PUBLIC WORKS

9380 SAN BENITO AVENUE, GERBER, CA 96035

P.: (530) 385-1462 F: (530) 385-1293

[HTTP://WWW.TEHAMACOUNTYPUBLICWORKS.CA.GOV/](http://www.tehamacountypublicworks.ca.gov/)

### ADDENDUM #2

#### TEHAMA COUNTY BUS SHELTER INSTALLATION PROJECT PLANS AND SPECIAL PROVISIONS COUNTY PROJECT NUMBER: 973037

- Addenda Issuance Date: March 26, 2015
- Bid Opening Date/Time: April 1, 2015 at 3:00 PM

#### **ADDENDUM #2; ITEM A:**

Refer to the project plans. Site 4 at Red Bluff City Hall has been relocated approximately 330' westerly to the corner of Oak St. and Madison St. Some estimated quantities have changed.

Replace plan sheet P-4, page 14 of 37 with attached "Exhibit 2-A"

#### **ADDENDUM #2; ITEM B:**

Refer to the project plans. The concrete pad at Site 8, Chevron Gas Station, has been lengthened from 20 feet to 22 feet. Some estimated quantities have changed.

Replace plan sheet P-8, page 18 of 37 with attached "Exhibit 2-B"

#### **ADDENDUM #2; ITEM C:**

Refer to the project plans. Site 9 at Greenville Rancheria has been relocated approximately 30' northerly on Montgomery Rd. Some estimated quantities have changed.

Replace plan sheet P-9, page 19 of 37 with attached "Exhibit 2-C"

#### **ADDENDUM #2; ITEM D:**

Refer to the project plans. Site 10 at Vista Way and Hornbeck St. has been relocated approximately 290' westerly to the corner of Vista Way and Bidwell St. Some estimated quantities have changed.

Replace plan sheet P-10, page 20 of 37 with attached "Exhibit 2-D"

#### **ADDENDUM #2; ITEM E:**

Refer to the project plans. Site 23 at 99W and Proberta has been relocated approximately 250' northwesterly on Flores Ave. Some estimated quantities have changed.

Replace plan sheet P-23, page 33 of 37 with attached "Exhibit 2-E"

#### **ADDENDUM #2; ITEM F:**

Refer to the project plans. Site 26 at Dollar Tree has been relocated approximately 110' easterly. Some estimated quantities have changed.

Replace plan sheet P-26, page 36 of 37 with attached "Exhibit 2-F"

#### **ADDENDUM #2; ITEM G:**

Refer to the project plans. The concrete pad at site 27, Shell Gas Station, has been widened from 8 feet wide to 10.5 feet wide. Some estimated quantities have changed.

Replace plan sheet P-27, page 37 of 37 with attached "Exhibit 2-G"

#### **ADDENDUM #2; ITEM H:**

Refer to the project plans. An additional site has been added. Concrete pad and Type 1 curb improvements shall be added to the existing bus stop location located approximately 160 feet south of Luther Rd. in Red Bluff.

Project plans shall now include page P-28 "Exhibit 2-H"

#### **ADDENDUM #2; ITEM I:**

Refer to the Bid Item List in the project Bid Book. Bid Item 28 "Walgreens" has been added.

Replace page B-3 of 12 with attached "Exhibit 2-I"



## TEHAMA COUNTY PUBLIC WORKS

9380 SAN BENITO AVENUE, GERBER, CA 96035

P.: (530) 385-1462 F: (530) 385-1293

[HTTP://WWW.TEHAMACOUNTYPUBLICWORKS.CA.GOV/](http://www.tehamacountypublicworks.ca.gov/)

### **ADDENDUM #2; ITEM J:**

Refer to the standard details in the project plans.

Class 2 Aggregate Base OR sand may be used as sub base for all concrete flat work, curbs and gutters.

### **ADDENDUM #2; ITEM K:**

Refer to the standard details in the project plans.

Type 1 and Type 2 curbs may be constructed monolithically.

### **ADDENDUM #2; ITEM L:**

Refer to the Bid Book and Caltrans Standard Specification. Section 59-6 "Painting Concrete" shall apply. Delete second sentence.

### **CONFIRMATION OF ADDENDA RECEIPT**

Be sure to acknowledge your receipt of this addendum on the Bid Signature Page to remain as a responsive bidder.

Tehama County Public Works

Signature: Kevin Rosser

Name: Kevin Rosser, PE


Title: Senior Civil Engineer of Public Works

Date: 3.26.15

SITE 4- OAK ST. AT MADISON ST.  
 LOCATION: EAST BOUND OAK ST., RED BLUFF  
 (APPROX. 35' EAST OF MADISON ST.)



ADDENDA EXHIBIT 2-A



- NOTES:**
- 1) REMOVE EXISTING PAVEMENT AT LOCATION OF PROPOSED PAD.
  - 2) CONC PAD MUST MATCH LONGITUDINAL SLOPE OF EXISTING CURB AND SLOPE TOWARDS ROADWAY AT 2% MAX SLOPE.
  - 3) SCORE CONC AS SHOWN.
  - 4) REMOVE EXISTING TRANSIT SIGN AND POLE AT THE CORNER OF OAK ST. AND WASHINGTON ST. MOUNT SIGNS PER DETAIL X-5.
  - 5) PAINT CURB RED AS DIRECTED BY ENGINEER.
  - 6) QUANTITIES SHOWN IN THE TABLE BELOW ARE FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM ACTUAL QUANTITIES.

QUANTITIES

TYPE 2 SHELTER	EA	1	6, X-5
CONC PAD	CY	3.84	4, X-3
REMOVE PAVEMENT	SF	175	--
MARKING PAINT	LF	40	--

TEHAMA COUNTY BUS  
 SHELTER PROJECT

SITE 4  
 LAYOUT PLAN

SCALE	HORIZ: 1" = 10'
	VERT: 1" = 10'
DRAWN BY:	NDC
DATE:	3/26/2015
CHECKED BY:	KR
DATE:	3/26/2015



TEHAMA COUNTY  
 PUBLIC WORKS


9380 San Benito Ave.  
 Gerber, Ca 96035  
 (530) 385-1462

P-4	14	37
SHEET NO.		PAGE NO.
PROJECT NO:		
973037		

**SITE 8- CHEVRON GAS STATION**  
**LOCATION: SOUTH BOUND S. MAIN ST. AT RAYLEY'S SHOPPING CENTER**  
**(APPROX. 175' WEST OF S. MAIN ST.)**



**ADDENDA EXHIBIT 2-B**



- NOTES:**
- 1) LOCATION OF PAD TO BE MARKED BY COUNTY
  - 2) CONSTRUCT TYPE 1 CURB TO RETAIN ADJACENT MATERIAL AT BACK OF SHELTER.
  - 3) PAD MUST MATCH LONGITUDINAL SLOPE OF (E) WESTERLY CURB WITH SLOPE TOWARD ROADWAY NOT EXCEED 2%.
  - 4) ACQUIRE TRANSIT SIGN FROM COUNTY. INSTALL SIGN TO SHELTER PER DETAIL X-4.
  - 5) BACKFILL AROUND PAD/CURB TO MATCH EXISTING ADJACENT MATERIAL.
  - 6) RELOCATE IRRIGATION AS NEEDED. SEE SPECIFICATIONS FOR MORE INFORMATION.
  - 7) REMOVE EXISTING BENCH FROM CURRENT LOCATION ON SOUTHERN END OF SITE. RETURN TO COUNTY STORAGE YARD.

**QUANTITIES**

ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY	DETAIL
TYPE 1 SHELTER	EA	1	5, X-4
CONC. PAD	CY	2.21	1, X-1
SIDEWALK EXPANSION	CY	0	4, X-3
TYPE 1 CURB	LF	20	2, X-2
REMOVE BENCH	LS	1	--
RELOCATE IRRIGATION	LS	1	--

**TEHAMA COUNTY BUS SHELTER PROJECT**

**SITE 8 LAYOUT PLAN**

**SCALE**

HORIZ: 1" = 10'  
 VERT: 1" = 10'

**DRAWN BY:** NDC  
**DATE:** 3/26/2015  
**CHECKED BY:** KR  
**DATE:** 3/26/2015



**TEHAMA COUNTY PUBLIC WORKS**

9380 San Benito Ave.  
 Gerber, Ca 96035  
 (530) 385-1462

P-8 18 <sup>37</sup>


**SHEET NO. PAGE NO.**

**PROJECT NO:**  
 973037

**SITE 9- GREENVILLE RANCHERIA**  
**LOCATION: SOUTH BOUND MONTGOMERY RD., RED BLUFF**  
**(APPROX. 100' NORTH OF KIMBALL RD.)**



ADDENDA EXHIBIT 2-C



MONTGOMERY RD.



**NOTES:**

- 1) APPROXIMATE LOCATION SHOWN. ACTUAL LOCATION OF SIDEWALK EXPANSION TO BE MARKED BY COUNTY
- 2) CONC MUST BE FLUSH WITH AND MATCH LONGITUDINAL SLOPE OF ADJACENT CURB AND SIDEWALK.
- 3) RELOCATE EXISTING IRRIGATION AS NEEDED. SEE SPECIFICATIONS FOR MORE INFORMATION.
- 4) SCORE CONC TO ALIGN WITH ADJACENT SIDEWALK.
- 5) PAINT CURB RED AS DIRECTED BY ENGINEER.
- 6) REMOVE EXISTING BENCH LOCATED 85' SOUTH AND RETURN TO COUNTY.
- 7) REMOVE EXISTING TRANSIT POLE AND SIGNS LOCATED 85' SOUTH AND MOUNT SIGNS TO SHELTER.
- 8) QUANTITIES SHOWN IN THE TABLE BELOW ARE FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM ACTUAL QUANTITIES.

**QUANTITIES**

ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY	DETAIL
TYPE 1 SHELTER	EA	1	5, X-4
SIDEWALK EXPANSION	CY	1.48	4, X-3
RELOCATE IRRIGATION	LS	1	---
MARKING PAINT	LF	60	---
REMOVE EXISTING BENCH	LS	1	---
REMOVE EXISTING SIGN	LS	1	---

**TEHAMA COUNTY BUS SHELTER PROJECT**

SITE 9  
LAYOUT PLAN

SCALE  
 HORIZ: 1" = 10'  
 VERT: 1" = 10'  
 DRAWN BY: NDC  
 DATE: 3/26/2015  
 CHECKED BY: KR  
 DATE: 3/26/2015



**TEHAMA COUNTY PUBLIC WORKS**

9380 San Benito Ave.  
 Gerber, Ca 96035  
 (530) 385-1462


P-9 19 37

SHEET NO. PAGE NO.  
 PROJECT NO:  
 973037

**SITE 10- VISTA WAY @ BIDWELL ST.  
LOCATION: WEST BOUND VISTA WAY, RED BLUFF  
(APPROX. 60' EAST OF BIDWELL ST.)**



**ADDENDA EXHIBIT 2-D**



**NOTES:**

- 1) APPROXIMATE LOCATION SHOWN. ACTUAL LOCATION OF PAD TO BE MARKED BY COUNTY
- 2) REMOVE EXISTING BENCH AND TRANSIT SIGN POLE LOCATED APPROXIMATELY 300 FEET TO THE EAST. RETURN BENCH TO COUNTY STORAGE YARD. MOUNT SIGNS TO SHELTER PER DETAIL X-4
- 3) SAW CUT AND REMOVE 10' SECTION OF EXISTING CURB AND GUTTER AT RAMP LOCATION (HATCHED). CONSTRUCT NEW CURB AND GUTTER. SLOPE NEW CURB TO MATCH 1:12 MAX SLOPE OF RAMP. MAINTAIN FLOWLINE OF EXISTING GUTTER. PAINT CURB RED AS DIRECTED.
- 4) PAD MUST MATCH LONGITUDINAL SLOPE OF EXISTING CURB AND HAVE 2% MAX CROSS-SLOPE TOWARDS ROADWAY
- 5) CONSTRUCT RETAINING STRUCTURE AS NEEDED TO RETAIN LANDSCAPE MATERIAL BEHIND CONCRETE PAD.
- 7) SCORE CONC. AS SHOWN ON PLANS.
- 8) RAMP SHALL MEET CURRENT ADA STANDARDS.
- 9) PROVIDE TACTILE SCORING AND TRUNCATED DOMES AT RAMP PER CALTRANS 2010 STANDARD PLANS, DETAIL A88A.
- 10) QUANTITIES SHOWN IN THE TABLE BELOW ARE FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM ACTUAL QUANTITIES.

**QUANTITIES**

ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY	DETAIL
TYPE 1 SHELTER	EA	1	5, X-4
CONC. PAD	CY	1.99	1, X-1
CONC. RAMP AND LANDING	CY	0.49	A88A
TYPE 1 CURB	CY	0.31	2, X-2
CURB AND GUTTER	CY	0.6	4, X-3
DETECTABLE WARNING SURFACE	SF	16	A88A
REMOVE SIGN POLE	LS	1	---
REMOVE PAVING	SF	25	---
REMOVE BENCH	LS	1	---
MARKING PAINT	LF	60	--
RETAINING STRUCTURE	LF	30	X-2

**TEHAMA COUNTY BUS  
SHELTER PROJECT**

**SITE 10  
LAYOUT PLAN**

SCALE	HORIZ: 1" = 10'
	VERT: 1" = 10'
	DRAWN BY: NDC
	DATE: 3/26/2015
	CHECKED BY: KR
DATE: 3/26/2015	



**TEHAMA COUNTY  
PUBLIC WORKS**

9380 San Benito Ave.  
Gerber, Ca 96035  
(530) 385-1462

P-10	37
20	
SHEET NO.	PAGE NO.
PROJECT NO:	
973037	

**SITE 23- PROBERTA**  
**LOCATION: EAST BOUND FLORES, PROBERTA**  
**(APPROX. 200' WEST OF 99W)**




ADDENDA EXHIBIT 2-E



EASTERLY VIEW

F L O R E S   A V E



**NOTES:**

- 1) APPROXIMATE LOCATION SHOWN. ACTUAL LOCATION TO BE MARKED BY COUNTY.
- 2) PAD SHALL HAVE 2% MAX CROSS-SLOPE TOWARD ROAD.
- 3) ACQUIRE TRANSIT SIGNS (2) FROM COUNTY AND MOUNT TO SHELTER PER DETAIL X-4.
- 4) SCORE CONC. AS SHOWN
- 5) BACKFILL AROUND CONC. PAD TO EXISTING ADJACENT MATERIAL. 4:1 SLOPE MAX. ENSURE POSITIVE DRAINAGE AWAY FROM PAVED SURFACE.
- 6) QUANTITIES SHOWN IN THE TABLE BELOW ARE FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM ACTUAL QUANTITIES.

**QUANTITIES**

ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY	DETAIL
TYPE 1 SHELTER	EA	1	5, X-4
CONC. PAD	CY	3.4	1, X-1
REMOVE PAVEMENT	SF	21	--
DETECTABLE WARNING SURFACE	SF	60	A88A

**TEHAMA COUNTY BUS SHELTER PROJECT**

**SITE 23 LAYOUT PLAN**

SCALE	HORIZ:	NTS
	VERT:	NTS
DRAWN BY:		NDC
DATE:		3/26/2015
CHECKED BY:		KR
DATE:		3/26/2015



**TEHAMA COUNTY PUBLIC WORKS**

9380 San Benito Ave.  
 Gerber, Ca 96035  
 (530) 385-1462

P-23		37	
33		37	
SHEET NO.	33	PAGE NO.	37
PROJECT NO:		973037	


**SITE 26- DOLLAR TREE**  
**LOCATION: WEST BOUND SOLANO ST, CORNING**  
**(APPROX. 320' WEST OF LINCOLN ST.)**



**ADDENDA EXHIBIT 2-F**



EXISTING ADDRESS MONUMENT TO BE RELOCATED APPROXIMATELY 30 FEET TO THE EAST. CONTRACTOR SHALL CONSTRUCT AN ADDITIONAL ADDRESS MONUMENT (IN KIND) APPROXIMATELY 30 FEET TO THE WEST



- NOTES:**
- 1) APPROXIMATE LOCATION SHOWN. ACTUAL LOCATION OF SHELTER TO BE MARKED BY COUNTY
  - 2) REMOVE FULL WIDTH AND DEPTH OF EXISTING AC IN PARKWAY STRIP AS SHOWN.
  - 3) SIDEWALK EXPANSION SHALL BE FLUSH WITH ADJACENT CURB AND SIDEWALK. SCORE LINES SHALL ALIGN WITH THE ADJACENT SIDEWALK.
  - 4) ACQUIRE TRANSIT SIGNS (2) FROM COUNTY AND MOUNT TO SHELTER PER DETAIL 5, X-4.
  - 5) PAINT CURB AS DIRECTED BY ENGINEER.
  - 6) QUANTITIES SHOWN IN THE TABLE BELOW ARE FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM ACTUAL QUANTITIES.

**QUANTITIES**

ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY	DETAIL
TYPE 1 SHELTER	EA	1	5, X-4
SIDEWALK EXPANSION	CY	0.81	4, X-3
REMOVE PAVING	SF	66	---
RELOCATE ADDRESS MONUMENT	LS	1	---
CONSTRUCT ADDRESS MONUMENT	LS	1	---
MARKING PAINT	LF	40	---

**TEHAMA COUNTY BUS SHELTER PROJECT**

**SITE 26 LAYOUT PLAN**

SCALE  
 HORIZ: 1" = 10'  
 VERT: 1" = 10'  
 DRAWN BY: NDC  
 DATE: 3/26/2015  
 CHECKED BY: KR  
 DATE: 3/26/2015



**TEHAMA COUNTY PUBLIC WORKS**

9380 San Benito Ave.  
 Gerber, Ca 96035  
 (530) 385-1462

P-26 36 37  
 SHEET NO. PAGE NO.  
 PROJECT NO:  
 973037


**SITE 27- SHELL GAS STATION**  
**LOCATION: WEST BOUND ANTELOPE BLVD., RED BLUFF**  
**(APPROX. 85' EAST OF SALE LN.)**



**CALTRANS**  
**ENCROACHMENT PERMIT#**  
**0214-NBS-0304**

CONTACT THE CALTRANS OFFICE OF ENCROACHMENT PERMITS (FRED CHAFFIN) 5 DAYS PRIOR TO BEGINNING SITE WORK TO SCHEDULE A PRE-CONSTRUCTION MEETING. (530)604-0387 REFER TO ENCROACHMENT PERMIT FOR ADDITIONAL PROVISIONS.

**ADDENDA EXHIBIT 2-G**



**NOTES:**

- 1) APPROXIMATE LOCATION SHOWN. ACTUAL LOCATION OF PAD TO BE MARKED BY COUNTY
- 2) SAW CUT AND REMOVE EXISTING SIDEWALK AT PROPOSED PAD LOCATION.
- 3) RELOCATE EXISTING IRRIGATION. SEE SPECIAL PROVISIONS FOR MORE INFORMATION.
- 4) ACQUIRE TRANSIT SIGNS (2) FROM COUNTY AND MOUNT TO SHELTER PER DETAIL 5, X-4.
- 5) PAINT CURB RED AD DIRECTED BY ENGINEER.
- 6) QUANTITIES SHOWN IN THE TABLE BELOW ARE FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM ACTUAL QUANTITIES.

**QUANTITIES**

ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY	DETAIL
TYPE 1 SHELTER	EA	1	5, X-4
CONC. PAD	CY	2.76	1, X-1
REMOVE PAVING	SF	158	--
RELOCATE IRRIGATION	LS	1	--
MARKING PAINT	LF	100	--

**TEHAMA COUNTY BUS SHELTER PROJECT**

SITE 27  
LAYOUT PLAN

SCALE	HORIZ: 1" = 10'
	VERT: 1" = 10'
DRAWN BY:	NDC
DATE:	3/26/2015
CHECKED BY:	KR
DATE:	3/26/2015



**TEHAMA COUNTY PUBLIC WORKS**


9380 San Benito Ave.  
 Gerber, Ca 96035  
 (530) 385-1462

P-27		37	
SHEET NO.	37	PAGE NO.	37
PROJECT NO:			
973037			

**SITE 28- WALGREENS**  
**LOCATION: WEST BOUND ANTELOPE BLVD., RED BLUFF**  
**(APPROX. 160' SOUTH OF LUTHER RD.)**



ADDENDA EXHIBIT 2-H



**NOTES:**

- 1) APPROXIMATE LOCATION SHOWN. ACTUAL LOCATION OF PAD TO BE MARKED BY COUNTY
- 2) EXCAVATE AND REMOVE LANDSCAPING AS NEEDED FOR CONSTRUCTION OF PAD.
- 3) CONSTRUCT CURB TO HEIGHTS AS NEEDED TO RETAIN ADJACENT LANDSCAPE MATERIAL.
- 6) QUANTITIES SHOWN IN THE TABLE BELOW ARE FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM ACTUAL QUANTITIES.

**QUANTITIES**

ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY	DETAIL
CONC. PAD	CY	0.92	1, X-1
TYPE 1 CONC. CURB	LF	25	2, X-2
RELOCATE IRRIGATION	LS	1	--

**TEHAMA COUNTY BUS SHELTER PROJECT**

**SITE 28 LAYOUT PLAN**

SCALE	HORIZ: 1" = 10'
	VERT: 1" = 10'
DRAWN BY:	NDC
DATE:	3/26/2015
CHECKED BY:	KR
DATE:	3/26/2015



**TEHAMA COUNTY PUBLIC WORKS**

9380 San Benito Ave.  
 Gerber, Ca 96035  
 (530) 385-1462

P-28	
SHEET NO.	PAGE NO.
PROJECT NO: 973037	

## BID ITEM LIST

### ADDENDA EXHIBIT 2-I

Item No.	Item Description	Unit Meas.	Quantity	Amount
1	SITE 1- CASA RAMOS	LS	1	
2	SITE 2- DOUGLAS ST @ JOHNSON ST	LS	1	
3	SITE 3- VINEYARD CHRISTIAN FELLOWSHIP	LS	1	
4	SITE 4- RED BLUFF CITY OFFICE	LS	1	
5	SITE 5- ANTELOPE BLVD @ RIO ST	LS	1	
6	SITE 6- VILLA COLUMBIA APARTMENTS	LS	1	
7	SITE 7- JACKSON ST @ MUSICK AVE	LS	1	
8	SITE 8- CHEVRON GAS STATION	LS	1	
9	SITE 9- GREENVILLE RANCHERIA	LS	1	
10	SITE 10- VISTA WAY @ HORNBECK	LS	1	
11	SITE 11- FOOD MAXX	LS	1	
12	SITE 12- RED BLUFF APARTMENTS	LS	1	
13	SITE 13- CABERNET APARTMENTS	LS	1	
14	SITE 14- DOLLAR GENERAL	LS	1	
15	SITE 15- RED BLUFF FAIRGROUNDS	LS	1	
16	SITE 16- FRONTIER VILLAGE APARTMENTS	LS	1	
17	SITE 17- SUNSHINE MARKET	LS	1	
18	SITE 18- JILL'S MARKET	LS	1	
19	SITE 19- MILL CREEK SHOPPING CENTER	LS	1	
20	SITE 20- SB 99E @ TEHAMA VINA	LS	1	
21	SITE 21- C ST @ 3RD ST, CITY OF TEHAMA	LS	1	
22	SITE 22- GERBER MARKET	LS	1	
23	SITE 23- SB 99W IN PROBERTA	LS	1	
24	SITE 24- SAFEWAY ON SB EDITH AVE	LS	1	
25	SITE 25- US BANK ON EB SOLANO ST	LS	1	
26	SITE 26- DOLLAR TREE WB SOLANO ST	LS	1	
27	SITE 27- SHELL GAS STATION	LS	1	
28	SITE 28- WALGREENS	LS	1	

BID TOTAL: \_\_\_\_\_



**TEHAMA COUNTY PUBLIC WORKS BUS SHELTER INSTALLATION PROJECT  
PLAN HOLDERS LIST**

Bid Opening Date: March 18, 2015 3:00 PM

Non-Mandatory Pre-Bid Meeting: March 11, 2015 10:00 AM

Engineer's Estimate: \$80,000

Plans: \$40

#	Date	Company Name	Contact Name and email address	Mailing Address	Phone Number
1	2/26/2015	Darren Taylor Construction	Brom Barker brom@darrentaylorconstruction.com	5750 Pleasant View Drive, Anderson CA 96007	530-378-2211
2	3/2/2015	Hat Creek Construction	James Folsom james@hatcreekconstruction.com	24339 HWY 89 N. Burney, CA 96013	530-335-5501
3	3/3/2015	Dudley's Excavating	Paul paul@dudleysexcavating.com	PO Box 901 Gerber, CA 96035	530-385-1445
4	3/4/2015	Construction Marketing Data Group	Thanh Nguyen thanh.nguyen@cmdgroup.com	30 Technology Parkway S, Ste 100, Norcross GA 30092	630-288-7988
5	3/10/2015	DA Lampe Construction	Darren Lampe dalampeconst@comcast.net	PO Box 1218, Durham CA 95938	530-343-7442
6	3/11/2015	McCuen Construction	Ray Foster ray@mccueninc.com		530-526-3127
7	3/11/2015	Blaisdell Construction	Craig Blaisdell craig@blaisdellconstruction.com	PO Box 938, Anderson, CA 96007	530-365-4444
8					
9					
10					
11					
12					
13					
14					

**County of Tehama**  
**Department of Public Works**

---

**Non-Mandatory Pre-Bid Meeting**  
**For**

**Tehama County Bus Shelter Installation Project**  
**County Project #: 973037**

\*\*\*\*\*AGENDA\*\*\*\*\*

**March 11, 2015; 10:00AM**

**I. Welcome**

- A. All attendees please sign-in; provide contact info for potential addendums (none issued yet)

**II. Introductions**

- A. Tehama County personnel present  
B. Potential Bidders present; Name & Company

**III. General Information:**

- A. Project is State Funded- Transit Security Grant Program Funds  
B. Engineer's Estimate is \$80,000  
C. Sealed bid are due on or before March 18, 2015 at 3:00PM  
D. Submit the entire Bid Book at time of bid. If you need separate forms- copy and replace. For additional forms, copy and staple to appropriate page.  
E. The project is bid as a Base Bid Project with each project site is bid as Lump Sum (includes all work)  
F. Project utilizes Caltrans 2010 Standard Specifications and Plans  
G. Class A contracting license is required at time of award  
H. Contractor is responsible for 811 Underground Services Alert

**IV. Project Specific Information**

- A. 27 sites throughout Tehama County  
B. Engineer will mark location of concrete pads and/or sidewalk extensions  
C. Prior to closing any walkways consider public convenience.  
D. Engineer will check concrete forms for "general" layout prior to pour.  
E. Contractor is responsible for ensuring ADA compliance. No tolerance is permitted for exceeding minimum or maximum slope values.  
F. Sites constructed in Caltrans right-of-way are subject to additional provisions  
G. Submittal of concrete JMF is required; materials testing will be at the Engineer's discretion.  
H. Estimated Notice to Proceed: 4/23/2015 (However, this date may change)  
I. Number of working days: 75

**V. Questions?!**

- A. Questions previously received:  
    **Q:** Will there be a forklift available at County storage yards for loading shelters?  
    **A:** No. Contractor is responsible for all loading and mobilization  
    **Q:** Are all shelters preassembled?  
    **A:** No. Refer to Section 10 "General" of the Special Provisions and Plan Sheets X-4 and X-5 for info  
    **Q:** Will there be materials testing?  
    **A:** Maybe. Testing will be at the Engineer's discretion  
    **Q:** When is the timeframe to begin work?  
    **A:** Estimated Notice to Proceed: 4/23/2015 (However, this date may change)
- B. New Questions?
- C. Post meeting questions can be directed to: Tehama County Public Works, Engineering Division  
Noel Carvalho: 530.385.1462 x3031
- D. Q & A list will be posted to the County website at:  
<http://www.tehamacountypublicworks.ca.gov/Engineering/projects.htm>

**County of Tehama  
Department of Public Works**

---

**Pre-Bid Meeting Q & A**

For

**Tehama County Bus Shelter Installation Project**

**County Project #: 973037**

**Bid Opening: March 18, 2015 at 3:00pm**

**9380 San Benito Ave, Gerber**

**Attendees:**

Barbara O'Keefe, Deputy Director- Tehama County Transportation Commission

Noel Carvalho, Assistant Engineer- Tehama County Public Works

Kevin Rosser, Senior Civil Engineer- Tehama County Public Works

**Contractors:**

Ray Foster- McCuen Construction

Al Garcia- Darren Taylor Construction

Forrest Gochring- G&S Construction

**Q:** Will there be a forklift available at County storage yards for loading shelters?

**A:** No. Contractor is responsible for all loading and mobilization

**Q:** Are all shelters preassembled?

**A:** No. Refer to Section 10 "General" of the Special Provisions and Plan Sheets X-4 and X-5 for info

**Q:** Will there be materials testing?

**A:** Maybe. Testing will be at the Engineer's discretion

**Q:** When is the timeframe to begin work?

**A:** Estimated Notice to Proceed: 4/23/2015 (However, this date may change)

**Q:** Can Type 1 and Type 2 curbs shown on detail sheet X-2 be constructed and poured monolithically?

**A:** Yes

**Q:** How was the project estimated?

**A:** Each site was individually estimated based on required labor and materials using costs from Caltrans and other historic cost data. Estimated quantities are provided on each plan sheet for "convenience only." Actual quantities must be confirmed by the contractor. Some sites require more or less work e.g.:

- assembly and installation of a shelter on existing concrete (no flatwork)
- assembly and installation of a shelter on new concrete (may require demo existing concrete, install new curb and gutter, relocate existing irrigation, etc.)

**Q:** Does the County already have the shelters?

**A:** Yes. Refer to Section 10 "General" of the Special Provisions and Plan Sheets X-4 and X-5 for info

Have New Questions?

Contact Noel Carvalho, Assistant Engineer at: 530.385.1462 x3031 or [ncarvalho@tcpw.ca.gov](mailto:ncarvalho@tcpw.ca.gov)

For more information visit: <http://www.tehamacountypublicworks.ca.gov/Engineering/projects.htm>

**County of Tehama  
Department of Public Works**

---

**Pre-Bid Meeting Q & A**

For

**Tehama County Bus Shelter Installation Project**

**County Project #: 973037**

**Bid Opening: March 18, 2015 at 3:00pm**

**9380 San Benito Ave, Gerber**

(Updated 3/26/2015)

**Attendees:**

Barbara O'Keefe, Deputy Director- Tehama County Transportation Commission

Noel Carvalho, Assistant Engineer- Tehama County Public Works

Kevin Rosser, Senior Civil Engineer- Tehama County Public Works

**Contractors:**

Ray Foster- McCuen Construction

Al Garcia- Darren Taylor Construction

Forrest Gochring- G&S Construction

**Q:** Will there be a forklift available at County storage yards for loading shelters?

**A:** No. Contractor is responsible for all loading and mobilization

**Q:** Are all shelters preassembled?

**A:** No. Refer to Section 10 "General" of the Special Provisions and Plan Sheets X-4 and X-5 for info

**Q:** Will there be materials testing?

**A:** Maybe. Testing will be at the Engineer's discretion

**Q:** When is the timeframe to begin work?

**A:** Estimated Notice to Proceed: 4/23/2015 (However, this date may change)

**Q:** Can Type 1 and Type 2 curbs shown on detail sheet X-2 be constructed and poured monolithically?

**A:** Yes

**Q:** How was the project estimated?

**A:** Each site was individually estimated based on required labor and materials using costs from Caltrans and other historic cost data. Estimated quantities are provided on each plan sheet for "convenience only." Actual quantities must be confirmed by the contractor. Some sites require more or less work e.g.:

- assembly and installation of a shelter on existing concrete (no flatwork)
- assembly and installation of a shelter on new concrete (may require demo existing concrete, install new curb and gutter, relocate existing irrigation, etc.)

**Q:** Does the County already have the shelters?

**A:** Yes. Refer to Section 10 "General" of the Special Provisions and Plan Sheets X-4 and X-5 for info

**Q:** Are there specification for painting curbs?

**A:** Addendum #2 included specifications for painting concrete

Have New Questions?

Contact Noel Carvalho, Assistant Engineer at: 530.385.1462 x3031 or ncarvalho@tcpw.ca.gov

For more information visit: <http://www.tehamacountypublicworks.ca.gov/Engineering/projects.htm>